

BRUHATH BANGALORE MAHANAGARA

DASARAHALLI ZONE, DASARAHALLI DIVI

Name of Work Sinking Of Borewells and Providing Pump and motors and laying of pipe line T.Dasarahalli in Ward No: 15 (3Nos)		Est Rs.
Ward No.15		Grant :
Job No. :		P-Code:
Ward Estimate Reference No.	Sub-Division Office Estimate Ref No.	Division
AE /DAS/ /2015-16	AEE /T.Das/ /2015-16	EE/Das

Office of the Assistant Executive Engineer
T.Dasarahalli Sub-Division
Dasarahalli Zone, BBMP,
Bangalore.

BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Time of Work: Sinking Of Borewells and Providing Pump and motors and laying of pipe line T.Dasarahalli in Ward No: 15 (3Nos)

SI	Description Of Item	Unit	No	L	B	D	Est.Cost	RS	20.00	Lakhs	Amount
1	Geophysical survey geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the hand pumps, MWS or PWSS by vertical electrical sounding by adopting venner or schlumbergers method including reconnaissance suevey of geological formation Geophysical investigation of existing ground Water in the vicinity. its quality , quality & acceptability of the users indicating the location of the site recommended depth of casing pipe required to seal the tope unconsolidated formation including an extra depth 1.0 metre in consolidated formation for aquire proposed to be tapped propable yield and other information required including transportation of instrument and accessories to work site, engating technical personal and labour etc.,PRE- Bangalore Circle-2014-15 Page No-47 & 48 , Item No-9.4										
2	Sinking of Borewell of 165 mm clear using fast hydraulic rig of capacity 250 PSIG & above 900 CMF & abpve in al strata including over burden upto 22 m fixing of casing pipes, collars and cap with necessary cutting and threading including transporation of rig and supporting vehicles, screws charges and cost of consumable including yield testing at the final depth with a minimum working of compressor for one hour all as specified.,PRE- Bangalore Circle-2014-15, Page No-46, Item No-9.1.1 to 9.1.7	Each	3					3.00	1882.00	5646.00	
a	0.00 to 50.00 mtrs	Rmt	3								
b	50mtr to 100.00 mtr						150.00		306.00	45900.00	
c	100.00 to 150.00 mtr		3				150.00		400.00	60000.00	
d	150.00 to 200.00 mtr		3				150.00		445.00	66750.00	
e	200.00 to 250.00 mtr		3				150.00		470.00	70500.00	
f	250.00 to 300.00 mtr		3				150.00		544.00	81600.00	
g	300.00 to 325.00 mtr		3				150.00		583.00	87450.00	
3	Supply of ISI Mark 175mm Nominal bore ,plain end steel Casing pipe- grade of steel Fee 410 of wall thickness 5.4 mm thick confirming to IS 1387/1993 and manufactured by basic open hearth electric or basic oxygen process in random lenth of 5 to 7mtrs. Both ends threaded Confirming to IS 554/1985, One end fixed with a Socket Confirming to IS 4270:2001 and the other end with Screwed pipes . All pipes shall be reasonably free from defectes. The tube shall be reasonably straight should be with ISI marking, weighing 25.10kg/mtr. (Inclusive of all taxes) (PRED,2012-13 Page No.iii, item No-84)						75.00		622.00	46650.00	
a	Casing pipe	Rmt	3								
4	Additional rate on item No. 2 is allowed for drilling in over burden and folling casing pipes beyond 20mtrs, rate at 15% and beyond 30mtrs 30% on basic rate of Rs.306 is allowed (PRED,2012-13 Page No48 item No-9.1.1)						120.00		1325.00	159000.00	
a	Above 20 mtrs and Up to 30 mtrs at	Mtrs	3								
5	Providing 175 mm dia MS Collar (RDED SR page ii, item86)						30.00		45.90	1377.00	
	Each	3					30.00		150.00	4500.00	

6) provide 175mm dia caps per RDED SR P- 3 150.00 3000.00
 855

and delivery at site brand new Texmo / Innoval / Lubi / Sabar / Atalanta /
 / waterman / Radha make suitable vertical installation in 150mm dia.
 wells comprising of single stage or multistage CF pump close coupled by means
 of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with
 pure drinking water (Wet type) squirrel cage **submersible induction motor** suitable
 for operation of 3Ph, 50Hz. 380/44 volts AC supply fitted with required accessories
 such as suction. casing, suction strainers, sand guard Non return valve etc., complete
 the pump and motor shall form an integral unit with all the required fittings **15HP 30**
stage Kirloskar, Atlanta, Suguna, CRI & other equipment pump (PWD SR 15-16 Page
 No xxxxi, Item. No 33

	No	3			3.00	70600.00	211800.00
8	Supplying and Drawing 3 core Flat PVC Shalted Submersible Pump Cable Manufactured with Electrolytic Grade Copper with Flexible copper conductor to table 3 class 5 of IS 8130-1984 and Virgen PVC insulation and Sheated Suitable for working Voltage Upto 1100 Volts BWSSB SR 2012-13, P-535, I. 30				1860.00	159.50	296670.00
	Mtrs	3x2	310.00				
9	Supplying and fixing 50mm Non Return Vavle of vertical type of approved make including cost of all materials labour HOM of equipment with all leads Complete as per Specification PWD SR 2015-16, P.No-XXIII, SI No.659 Code No.0126				3.00	1145.00	3435.00
	Nos	3					
10	Supplying and fixing 50mm GM Gate Vavle PWD SR 15-16, SI No.673, P.No- XXIII Code No.0164)				3.00	1600.00	4800.00
	Nos	3					
11	Supplying and fixing 175mm Borewell cap with clampset As per approved Rate per SERED Letter No 2081/2010-11, Dt.28.7.2010,				3.00	500.00	1500.00
	Nos	3					
12	Supplying and fixing 50mm GI Union PWD SR 2015-16, P.No.XXXVII,				3.00	223.70	671.00
	Nos	3					
13	Supplying and fixing 50mm GI Elbow PWD SR 2015-16, P-XXXVII				9.00	111.80	1006.00
	Nos	3	3.00				
15	Supplying and delivery at site brand new star / Essen / Lotus / Sun shines / Adharsh / GK Controls best indigenous make combined energy meter cum control panel board unit of size 1200x600x350mm minimum mechanically strong vernin and water proof. The unit shall have two detachable doors suitable for operation on 3ph, 50 hz, 380/440 volts, AC supply with spring loaded latch, locking device with a key ribs should be provided inside the door canopy apron and louvers ventilators shall be provided the combined energy meter cum control panel board unit suitable for operation on 3ph, 50 hz, 380/440 volts AC supply shall be consists etc., complete the panel board shall be consist etc., complete the panel board shall be fabricated on single unit in the above componets panel board for suitable pumpset with star delta star retr out door type 10hp to 15 hp PRED ISSUE RATE				3.00	10000.00	30000.00
	Nos	3					
16	Providing and fixing of 50mm G.I pipe 'C' class heavy duty for erection of submersible pumpset galvanised tube 50mm supply ad delivery of cause heavy duty as per IS/239/1990 (PRED SR P No.56, I.No 10.1)				870.00	519.30	451791.00
	Mtrs	3	290.00				
17	Erection of combined panel board and meter unit with necessary materials and labour including providing cement concrete foundation bed cont door type etc., complete PRED ISSUE RATE				3.00	475.00	1425.00
	Nos	3					
18	Supplying of TPST with rewirable porcelain channels in SM encloser 15/32 amps P- 521, Group-Bi-1(b), BWSSB SR 2013-14.				3.00	1320.00	3960.00
	Nos	3					

Signature

15

18
SI

17

16

	ing and fixing 500x500x65mm polished wood board made up not less than in thick plank in front plank one end provided for olding at other end fixing the of the valve using through bolts and nuts. PRED ISSUE RATE	Nos	3		3.00	302.50	908.00
	Supplying and fixing LED Type panel board indicating lamp with required colour suitable for 220 v AC 50Hz 12/24 V DC Group B, P-529, I-35(b), BWSSB SR 2013-14.	Nos	3	3.00	9.00	385.00	3465.00
21	Supplying and drawing each PVC insulated 650/100 V grade wire in the conduct (Open or Concealed system of wiring) 7/20 or 7/36 copper wire. P-380, I-20, II(d), BWSSB SR2012-13.	Nos	3	10.00	30.00	27.50	825.00
22	Supplying, fixing and wiring heavy duty low voltage capacitors confirming to I 2834, 3 PHASE 400/440 Volts grade for power factor improvement of rotating machinery capacitor in KVAR - rating Nos 2 KVAR Capacity P-402, I-34(a), BWSSB SR 2012-13.	Group A Nos	3		3.00	385.00	1155.00
23	Supplying and fixing miniature Circuit breakers on existing MCB distribution boards using necessary fixing materials and wiring complete as required P-526, I-13 (P, a), BWSSB SR 2013-14.	Nos	3		3.00	880.00	2640.00
24	Supplying, fixing, wiring earth electrode for grounding conduits, LC cutouts and other equipments on the meter board using 40mm dia 2.90mm thick GI pipe 2.50m long buried in a pit. The pit should be filled with equal proportion of soft and charcoal 150mm around the pipe to complete depth. the connection from the pipe to the conduct etc., is to be established through GI wire of size as per ISI specifications 7.3.3 IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122mm dia P-552, I-7, BWSSB SR 2013-14.	Nos	3		3.00	1650.00	4950.00
25	Supplying and fixing class A (medium duty) GI pipe wall thickness not less than 3.25mm on pole. P-555, I-15, BWSSB SR 2013-14.	Nos	3	10.00	30.00	286.00	8580.00
26	Supplying and fixing wiring earth electrode for grounding conduits, LC cutouts and other equipments on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 Mtr long buried in a pit./ the pit should be filled with equal proportion of salt and charcoal 150mm around the pipe to complete depth the connections from the pipe to the conduits etc., is to be established through GI wire of size as per ISI specification 7.3.3 of ISI 732 using 12 mmdia bolts, nuts washers and checknuts etc., the pipe shall have 16 through holes of 122mm dia (P.No.552, I.No.7, BWSSB SR 13-14)	Nos	3		3.00	1650.00	4950.00
27	Supply 1.1 KV class UG cable from nearest BESCOM pole to panel board including earth work and road restoratio 4 core 16 sqmm. P-426, I-10(d), BWSSB SR 2012-13.	Mtrs	3	30.00	90.00	165.00	14850.00
28	Labour charges for laying 1.1 KV class UG cable when supplied by agencies in existing trenches GI pipe / stoneware pipe/ on pole as required, P-427, I-11 (a), BWSSB SR 2012-13.	Mtrs	3	30.00	90.00	5.50	495.00
29	Digging of trench of 0.6m deep x 0.5m wide refilling the trench to the required level and consolidating etc, complete P-427, I-12 (a), BWSSB SR2012-13.	Mtrs	3	15.00	45.00	44.00	1980.00

Signature

15

65mm polished wood board made up not less than 10mm and provided for olding at other end fixing the

202.50

908.00

and fixing LT cast iron pot heads suitable for 1.1 KV class 16 sqmm UG cable with necessary bitumen / insulating compound complete with terminalas, pins, bolts, nuts, washers etc., P-428, I-16(b), BWSSB SR 2012-13.

Supplying and fixing of porcelain fuse channel with cut-out on existing / new wooden panel using necessary nuts, bolts and washers etc., BWSSB SR P-394 I-173

32	BESCOM Deposit charge and miscellaneous.	Nos	3	6.00		18.00	440.00	7920.00
		L.S	3			3.00	15000.00	45000.00

33 Cutting of road surface for pipeline trenches and disposing of the excavated stuff as directed including barricading, danger lighting etc., in the Asphalt surface road. (Pg. No-272, I.No-37.38) PWD SR 2014-15

	Cum	3	250.00	0.60	0.15	67.50	311.64	21036.00
--	-----	---	--------	------	------	-------	--------	----------

34 Earthwork excavation for foundation of buildings water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. Noll KBS 2.1.C/2.9.4/2.18/2.19 (Pg. No-05, I.No-2.4) PWD SR 2014-15

	Cum	3	250.00	0.60	0.75	337.50	259.70	87649.00
--	-----	---	--------	------	------	--------	--------	----------

35 Providing and installing at site of work P.V.C pipes including cost of pipes and specials and labour including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe around to a depth not less than 15 cms with gravel or selected earth available from the excavation etc., complete PVC pipes of 6kg/5qm 75mm Dia. (Page NO-102, ITEM no-13.15 (b), of PRED SR 2012-13).

	Rmt	3	250.00			750.00	157.00	117750.00
--	-----	---	--------	--	--	--------	--------	-----------

36 Supplying and fixing 50 mm GI pipes 'B' class heavy duty (As PER bwssb Store issued Rate) **Note:-** GI Pipe using for Road crossing places.

	Mtrs	3	10.00			30.00	325.00	9750.00
--	------	---	-------	--	--	-------	--------	---------

37 Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5m. Including cost of all labour complete as per specification. (Pg. No-6, I.No-2.11 PWD SR 2013-14.)

	Cum					337.50	60.48	20412.00
--	-----	--	--	--	--	--------	-------	----------

38 Transportation of pumping machineries PRE SR 2012-13 PG 51/10.3.19

						3.00	900.00	2700.00
--	--	--	--	--	--	------	--------	---------

39 Erection of Pumping machineries PRE SR 2012-13 PG 51/10.3.20

						3.00	900.00	2700.00
--	--	--	--	--	--	------	--------	---------

40 Miscellaneous and rounding off **+ 1% O.C.**

						L.S	3449.16	2762.00
						TOTAL		200000.00

(Rupees Twenty Lakhs Only)


CERTIFICATE:-

- 1 The Work spot has been inspected and the work is found to be necessary
- 2 The Estimate is prepared as per the PW,P & IWTD -SR-2014-15 & PRED SR 2012-13 & BWSSB SR 2012-13
- 3 The Provision made in estimate are adequate and essential.
- 4 This area comes under BBMP limits.

25.08.2015
Assistant Engineer
Ward-15

25.08.2015
Asst. Exe. Engineer
T.Dasarahalli Sub-Division
B.B.M.P.

25.08.2015
Executive Engineer
Dasarahalli Division
B.B.M.P. Bangalore.



P.T.O.
For As

CE/02/14/34/15-16 ದಿ.04/01/2016

ನಂ. 99: 44

ದಿನಾಂಕ :


ರೂ. Rs. 200000/- (ದ. ಲಕ್ಷ 200000/-)

ಅಂದಾಜು ಪಟ್ಟಿ ಅಡಕತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ.

ಮುಖ್ಯ ಅಧಿಕಾರಿಗಳು

ಮಾ.ಎಂ.ಸಿ.

ದಾಸರಹಳ್ಳಿ ಪಂಚಾಯತ್, ಬೆಂಗಳೂರು.



One all se

ಇ ದಾಖಲೆಗಳು ಉಚಿತ ದಾಖಲೆ
ಮಹತ್ವ ಪಡೆಯುವ ಮಹತ್ವದ ದಾಖಲೆ

SRK
Vijay
Mol
web